

On-site Wastewater Treatment System Environment Discharge Performance Appraisal

For the RX Plastics AirTech 9000 NR



Prepared by Sam Weiss and Paul Scholes

December 2007
EDPA 005/07

5 Quay Street
P O Box 364
Whakatane
NEW ZEALAND

*Working with our communities for a better environment
E mahi ngatahi e pai ake ai te taiao*

Acknowledgements

Thanks to Andy Bainbridge, Dave Anderson and the rest of the team at the Rotorua District Council Wastewater Treatment Plant for their considerable effort in making this trial possible.

Disclaimer

This document reports on the measured ability of the wastewater treatment system to reduce the concentration of a range of wastewater parameters. No testing was performed on the integrity, capacity or durability of this system.

For further information refer to:

- AS/NZS 1546.1:1998 – On-site domestic wastewater treatment units Part 1: Septic tanks.
- AS/NZS 1547:2000 – On-site domestic wastewater management.
- AS/NZS 1546.3:2001 – On-site domestic wastewater treatment units Part 3: Aerated wastewater treatment systems.

Summary

The RX **Plastics AirTech 9000 NR** wastewater treatment system had influent and effluent monitored every six days over a nine month period. The best performing 16 consecutive samples (over about three months) within this was used for evaluating nitrogen reduction. Three blocks of seven consecutive days (week 8, 16, and 25) were also sampled to determine carbonaceous biochemical oxygen demand, and total suspended solids.

Effluent discharged from this treatment system was found to comply with Environment Bay of Plenty's standard for the Rotorua lakes' catchment.

This system may be installed anywhere in the Bay of Plenty region, including the Rotorua Lakes' catchments, provided all conditions of rule 13 are met.

It also performed within the limits set by Environment Waikato for the Taupo catchment.

Before choosing a wastewater system it is recommended that power consumption and maintenance requirements are carefully considered.

Contents

Acknowledgements	i
Disclaimer	iii
Summary	v
1 Introduction	9
2 System information	9
3 System specifications	10
4 Testing regime	10
5 Test Results	11
5.1 CBOD ₅ , Faecal Coliform and TSS Test Results	12
5.2 Other Results	13
5.3 Electricity Consumption	13
5.4 Daily Volume	13
6 Compliance Statement	14
7 Compliance Standard	14
Appendix – Performance Certificate	15

1 Introduction

Excessive levels of nutrients in waterbodies are a known risk factor for their eutrophication. One source of these nutrients, particularly nitrogen, is from on-site wastewater treatment systems.

Many local authorities are interested in an assessment of the effectiveness of advanced (aerobic) wastewater treatment systems (compared to conventional septic tanks) for where no reticulated sewerage system exists. Some regional plans, eg. Environment Bay of Plenty and Environment Waikato, specify levels of treatment required by advanced wastewater treatment systems. Many other areas are likely to follow as water quality comes under increasing pressure.

A trial site was established at the site of the Rotorua wastewater treatment plant in 2005 to measure advanced wastewater treatment system performance. From 2005 to July 2007 fourteen different systems have been trialled. Another round of trials commenced November 2007.

This report presents the results for one of the trialled systems. Reports on the other systems are available at the Environment Bay of Plenty website www.envbop.govt.nz

2 System Information

System Name/Model:

RX Plastics AirTech 9000 NR

Manufacturer:

RX Plastics Ltd
PO Box 360
Ashburton
Email nevillem@rxplastics.co.nz

Supplier:

as above

3 System Specifications

Supplier	System	Rated Flow (l/day)	Tanks Operating Capacity*	Treatment Technology
RX Plastics Ltd	AirTech 9000 NR	2000	Primary Tank: 3300 litres Aeration & clarification & recirculation ¹ 4400 litres	Aerated wastewater treatment system

* In addition to this there is emergency storage of 1500 litres

4 Testing Regime

Untreated wastewater from Rotorua City's eastside sewer was screened before passing into a header tank from which influent was delivered to a number of wastewater treatment systems. Influent was pumped to the systems twice daily by positive displacement pumps operating from a single variable speed drive. The loading regime was intended to be approximately 1000 litres per day per system, with two thirds of the load delivered between 6 am and 11 am every morning and the balance between 6 pm and 9 pm at night. This regime was designed to simulate typical household usage.

The daily flow varied throughout the period largely due to the pumps being unable to reliably handle the raw influent and some blockages occurring.

Samples of influent and effluent were taken at about six day intervals for:

<ul style="list-style-type: none"> • pH and alkalinity • ammonium-nitrogen (NH₄-N) • nitrate-nitrogen (NO₃-N) • nitrite-nitrogen (NO₂-N) 	<ul style="list-style-type: none"> • total kjeldahl nitrogen (TKN) • total oxidised nitrogen (TOxN) • total nitrogen (TN) • total phosphorus (TP)
---	---

In addition to the regular interval sampling, there were three, seven consecutive day blocks of samples. These were analysed for the above parameters plus the following: carbonaceous biochemical oxygen demand (CBOD5), total suspended solids (TSS) and faecal coliforms (FC).

Analysis was performed by the Rotorua District Council Environmental Laboratory (IANZ accredited) in accordance with "Standard Methods for the Examination of Wastewater", APHA, AWWA, WPCF.

¹ Includes a pump chamber of 350 litres

Effluent from each wastewater treatment system was discharged into a 20 litre container placed within a 200 litre drum, from where it returned to the sewer. The drums were filled intermittently depending upon the individual system characteristics.

Samples were taken from the 20 litre container. This ensured that completely fresh samples were taken every time. Temperature of the effluent was measured in the outflow collection drums.

5 Test Results

Flow to the RX Plastics AirTech 9000 NR wastewater treatment system commenced on 16 October 2006. Sampling occurred from 26 October 2006 through to 26 July 2007.

The TN evaluation period is from 6 January 2007 to 10 April 2007. This is a period of 95 days. Nitrogen test results are based on data from sampling about every six days over the evaluation period. The above period was chosen for TN evaluation of this system as it reflects the best TN reduction performance over 16 consecutive samples.

The average measured flow to this system over the TN evaluation period was 819 litres per day, excluding one 'no flow' day (refer to Table 4).

Table 1 displays total nitrogen influent and effluent results for the evaluation period. All 16 effluent results over the evaluation period are 15 gm^{-3} or less with the average being 10.7 gm^{-3} . Based on the average of the 95 day TN evaluation period result, the system reduced nitrogen by 88%.

Table 1 Summary of total nitrogen results over the TN evaluation period

Date	Day	Influent (gm^{-3})	Effluent (gm^{-3})	Parameter	Influent (gm^{-3})	Effluent (gm^{-3})
6-Jan-07	1	105.1	13.4	n	16	16
12-Jan-07	7	78.5	14.7	mean	86.5	10.7
18-Jan-07	13	82.1	10.4	median	88.3	10.6
24-Jan-07	19	101.9	9.8	SD	27.6	1.7
30-Jan-07	25	69.9	8.4	Max	162.4	14.7
5-Feb-07	31	85.4	7.9	Min	45.0	7.9
12-Feb-07	38	93.3	10.8	lower quartile	69.8	9.7
18-Feb-07	44	48.8	10.9	upper quartile	97.7	11.3
24-Feb-07	50	96.4	12.0			
2-Mar-07	56	69.4	11.7			
8-Mar-07	62	162.4	9.8			
14-Mar-07	68	109.3	9.9			
20-Mar-07	74	50.7	9.3			
26-Mar-07	80	94.1	9.5			
1-Apr-07	86	45.0	11.0			
10-Apr-07	95	91.2	11.1			
Average		86.5	10.7			
Average TN Reduction		88%				




Figure 1 Graph of total nitrogen results over the TN evaluation period

5.1 CBOD₅¹, Faecal Coliform and TSS Test Results¹

Three one week (7 day) duration test periods at week 8, week 16, and week 25 were delineated for testing CBOD₅, TSS, FC and TN.

Table 2 Average influent and effluent results over seven days for weeks 8, 16 and 25

Influent	CBOD ₅ (gm ⁻³)	FC (cfu/100mL)	TSS (gm ⁻³)	TN (gm ⁻³)
Wk 8	532	1.5 X 10 ⁷	1692	70.1
Wk 16	246	3.7 X 10 ⁷	705	78.9
Wk 25	423	2.8 X 10 ⁷	1768	105.8

Effluent	CBOD ₅ (gm ⁻³)	FC (cfu/100mL)	TSS (gm ⁻³)	TN (gm ⁻³)
Wk 8	3.4	8.0 X 10 ³	2	13.5
Wk 16	2.3	6.7 X 10 ⁴	7	8.3
Wk 25	3.5	1.7 X 10 ⁴	3	11.6

Effluent	CBOD ₅ (gm ⁻³)	FC (cfu/100mL)	TSS (gm ⁻³)
Mean	3.0	3.3x 10 ⁴	4
Median	3.0	2.0 x 10 ⁴	3
SD	1.3	3.5 x 10 ⁴	3
n	18	19	18
Minimum	1.0	0.1 x 10 ⁴	1
Maximum	6.0	13.6 x 10 ⁴	12
Lower Quartile	2.0	1.0 x 10 ⁴	2
Upper Quartile	3.8	4.5 x 10 ⁴	5

¹Note that the CBOD values are likely to be lower than those presented in Table 2, due to treating results lower than the detection limit as being at the upper limit of detection

5.2 Other Results

Table 3 Statistics for nutrient data over the TN evaluation period

	TP (gm ⁻³)	NH ₄ -N (gm ⁻³)	NO ₃ -N (gm ⁻³)	NO ₂ -N (gm ⁻³)
Mean	9.0	1.2	7.0	0.24
Median	8.9	0.6	7.0	0.22
SD	1.1	1.6	1.6	0.2
n	16	16	16	16
Minimum	7.3	0.2	4.6	0.01
Maximum	11.6	6.4	10.5	0.62
Lower Quartile	8.3	0.5	6.0	0.13
Upper Quartile	9.8	1.0	7.9	0.33

5.3 Electricity Consumption

Electricity consumption of the RX Plastics AirTech 9000 NR wastewater treatment system averaged 5.3 kWh per day over the 95 day TN evaluation period.

There was a 600 watt irrigation pump present during the trial.

5.4 Daily Volume

Each system had a water meter to measure the daily volume of treated effluent discharged. Table 4 below shows the flow statistics for this system.

Table 4 Statistics for daily flow data over the TN evaluation period

	litres per day
Mean	819
Median	801
SD	284
n	91
Minimum	0
Maximum	1553
Lower Quartile	637
Upper Quartile	1090
Number of 'no flow' days ignored	1

Note:

Some 'no flow' days for all systems were caused by the pump controller failing to re-set after power failures. These 'no flows' were ignored for the purpose of calculating Table 4. Any other 'no flow' days unique to a particular system, caused by a blockage etc, were included.

6 Compliance Statement

The RX Plastics AirTech 9000 NR wastewater treatment system met the performance requirements for operating as a permitted activity within Bay of Plenty Region, including the Rotorua Lakes' catchments. It also performed within the limits set by Environment Waikato for the Taupo catchment.

Over a 95 day TN evaluation period all of the sixteen sample days were equal to or under 15 gm^{-3} total nitrogen, with the average being 10.7 gm^{-3} . Over this period the total nitrogen was reduced on average by 88 percent.

CBOD₅ and TSS maximum results were both well below Environment Bay of Plenty permitted maximums of 30 gm^{-3} and 45 gm^{-3} respectively.

The compliance statement relates only to the particular model described above, and on the basis that the key specifications are the same as those in the model tested. This includes tank and chamber volumes, re-circulation rates, and textile/film total surface area.

7 Compliance Standard

The performance standard for on-site wastewater treatment systems are based on the rules stated in Environment Bay of Plenty's Operative On-site Effluent Treatment Regional Plan 2006.

Discharges from on-site effluent treatment systems located within the Rotorua Lakes Catchments are described by rules 11 and 13 as a permitted activity provided that:

The effluent quality of systems after a maximum settling in period of six months does not exceed:

- a total nitrogen (TN) level of 15 grams per cubic metre as nitrogen;
- 30 grams per cubic metre of CBOD₅ and;
- 45 grams per cubic metre of suspended solids; prior to discharge to the dispersal system.

For installations outside Rotorua catchments the nitrogen limit does not apply.

Refer to rules 12 and 13 for compliance details for installations of new on-site wastewater treatment systems in the Bay of Plenty.

For confirmation of any details in this report please contact Sam Weiss at:

Environment Bay of Plenty
5 Quay Street, P O Box 364
Whakatane, New Zealand
ph. 0800 ENV BOP (368 267)

Appendix – Performance Certificate

Performance Certificate



Company:	RX Plastics Ltd
Address:	PO Box 360, Ashburton
Model Number:	AirTech 9000 NR
Manufacturer rated daily flow (litres)	2000
Total operating capacity, including pump chamber (litres)	7700
Primary tank (litres)	3300

This is to certify that the **AirTech 9000 NR** wastewater treatment system supplied by **RX Plastics Ltd** is considered to meet the requirements of rule 13(f) of the Operative On-Site Effluent Treatment Regional Plan 2006. Therefore it may be installed within the Rotorua Lakes Catchments as a permitted activity, provided that all other requirements of rule 13 are met.

The certification relates only to the particular model described above, on the basis that the key specifications are the same as those in the model tested at the Rotorua trial facility. This includes tank and chamber volumes, re-circulation rates, and media total surface area.

For any questions about this certificate please contact Sam Weiss on 0800 368 267.

Note: In order to comply with Regional Plan requirements Environment Bay of Plenty must be provided with written confirmation that a system has been installed to the manufacturer's specifications and that it fully meets the requirements of rule 13.

A handwritten signature in black ink, appearing to read 'S. Weiss'.

Sam Weiss
Project Implementation Officer
Environment Bay of Plenty

Date of Issue: 1 September 2007
Expiry date: 1 September 2012